

Safe Routes to Schools Improvement Plan
Covington Elementary School
Los Altos, CA


School Safety Assessment held February 2021



- 1 Covington at school driveway**
1a. Update school crossing sign to Assembly B with down arrow
1b. Construct raised crosswalk
1c. Install ADA ramps on both sides of sidewalk at loop
1d. Work with existing homeowner to trim vegetation at crosswalk
- 2 Covington Rd near Bellevue Ct**
2a. Install speed feedback sign
- 3 Covington Rd and Fremont Ave**
3a. Evaluate potential for roundabout
3b. Install crosswalk
- 4 Covington Rd and El Monte Ave**
4a. Extend the walk phase across El Monte Ave
4b. Construct curb extension on southeast corner
- 5 El Monte Ave**
5a. Add buffers to existing bike lane
- 6 El Monte Ave and Shirlynn Ct**
6a. Install crosswalk with pedestrian refuge island and RRFB
- 7 Giffin Rd**
7a. Construct pedestrian path to fill sidewalk gap
- 8 San Antonio Rd and Cuesta Dr/1st St**
8a. Install ADA ramps on all corners except northwest
8b. Install high-visibility crosswalk on free right turn lane, and evaluate potential for raised crosswalk
8c. Refresh all crosswalks
8d. Fix bike route sign facing wrong direction (east of intersection on north side of Cuesta Dr)
- 9 Cuesta Dr and Tyndall St**
9a. Move stop bar back on Tyndall St (north side)
- 10 Cuesta Dr and Lassen St**
10a. Reconstruct sidewalk where tree root has lifted concrete (east of Lassen)

continued

- NOTES:
- 1) The above items are recommendations only and based on Safe Routes to Schools site assessment best practices. Feasibility determination, final design, accessibility, funding, and implementation of any recommended improvements is the responsibility of the appropriate governing agency.
- 2) Red curb and/or parking restriction signage should be provided between advance stop/yield markings and the crosswalk. Exact red curb distance should be determined in accordance with the CA-MUTCD and City policies/standards.



continued from previous page

- 11

Cuesta Dr and Gabilan St
11a. Install RRFB and ADA ramps on east leg at existing high-visibility crosswalk
- 12

Cuesta Dr and El Monte Ave
12a. Install ADA ramps on northeast, southwest, and southeast legs of intersection
12b. Tighten turning radius on southwest corner
- 13

Arboleda Dr
13a. Install Assembly A school warning signage on Arboleda Dr
- 14

Cuesta Dr and Campbell Rd
14a. Install advance stop bars on west side of intersection
14b. Install ADA ramps
- 15

Arboleda Dr andh Campbell Rd
15a. Install high-visibility crosswalks, including potential enhancements such as median refuge or actuated beacon
- 16

Campbell Rd and Rosita Ave
16a. Update School Crossing signs to Assembly B with down arrow
- 17

Campbell Rd
17a. Construct pedestrian path
- 18

Clark Ave
18a. Repair and widen existing sidewalk / berm-protected walkway
- 19

Clark Ave and Cuesta Dr
19a. Install high-visibility crosswalk across Cuesta Dr, including potential enhancements such as median refuge or actuated beacon
19b. Install yellow transverse crosswalk on north leg of intersection

General Recommendations

- Conduct ADA Ramp Assessment
- Conduct sign audit to ensure all signs are current
- Add yellow reflector bands to all school signs